



Design Services Request For Proposal Activity
December 2, 2024

Project Name	Mail PSA RFP	Project Manager	Scope	Construction Estimate
P2-140 Truck Loading Bay Odor Control Improvements at Plant No. 2	Dec 2024	Omeed Pour	For the solids loading facility at Plant No. 2, this project includes improvements to the odor control system, lighting, cake silos structural repair, and drainage improvements to the loading station water drain.	\$4,400,000
P1-141 Administrative Facilities Demolition	Dec 2024	Hye Oh	This project will demolition existing Administration Building with the space repurposed to allow for additional parking.	\$2,600,000
7-69 North Tustin-Orange Sewer Improvements	Dec 2024	Cindy Murra	This project will upsize a portion of the North Trunk sewer system to increase hydraulic capacity and replace and rehabilitation portions of the North Trunk, Tustin-Orange Trunk, Yorba Street Sub-Trunk, Panorama Heights Sub-Trunk, Hewes Avenue Sub-Trunk, and Chapman Avenue Sewer within the City of Tustin, Orange, and Unincorporated Orange County. The project includes improvements to install 6,351 feet of 18-inch sewer with 60-inch manholes, replace 840 feet of 8-inch to 12-inch sewer, rehabilitate 4,544 feet of 8-inch to 27-inch sewer, construct 5 spot repairs, rehabilitate 127 manholes 48-inch to 72-inch in diameter, and abandon 146 feet of 12-inch sewer and a 48-inch manhole. In addition, the project includes constructing up to 1,000 LF of 20 foot wide access roads within OC San easement areas.	\$38,000,000
J-137 Ocean Outfalls Rehabilitation	Feb 2025	Victoria Pilko	This project will rehabilitate the 120-inch Ocean Outfall. It includes the removal of debris blocking diffusers access ports, replacing all hardware that reinforces pipe joints, the addition of ballast rock in shallow sections, replacement of existing manhole covers, removal of internal outfall sediment deposits, and the replacement of the flap gates. Also, this project will perform a detailed inspection, condition assessment, and essential rehabilitation of the 78-inch Emergency Outfall.	\$42,700,000
J-138 Central Generation Facilities and OOBs Seismic Upgrades	May 2025	Nasrin Nasrollahi	The buildings at Plant No. 1 and 2 that house electrical systems will undergo structural and geotechnical (soil) improvements to reduce the risk of failure during a significant seismic event. Plant No. 1 includes the Central Generation and Power Building 4. Plant No. 2 includes the Central Generation Building.	\$10,700,000
7-63 MacArthur Pump Station Rehabilitation	May 2025	Andrew Brown	The MacArthur Pump Station is adjacent to MacArthur Boulevard and north of Jamboree Road in the City of Newport Beach. This project includes structural rehabilitation of the sewer wet-well and underground electrical room and pump room. Replacement of mechanical equipment (e.g., pumps, valves, piping) and electrical and instrumentation equipment is also included.	\$9,300,000
J-139 Process Control System Alarm Optimization	Jun 2025	Justin Fenton	This project will install a new master alarm database that will be integrated with the existing process control system, develop an alarm configuration philosophy, and reconfigure all existing alarms. This project will also create dashboards and KPI reports for ongoing analysis of the alarm system.	\$2,500,000
P2-141 Headworks Electrical Distribution Improvements at Plant 2	May 2025	Jacob Dalgoff	Distribution Center H (DC-H) houses the electrical distribution equipment for the Headworks area. Switchgear and Motor Control Centers (MCCs) supply power and controls to all areas of Headworks including: Influent Metering, Influent Pump Station, Waste Sidestream Pumps, Bar Screens, Screenings Washing, Scrubbers, Biotower, Grit Basins, and Grit Handling. This project would replace and reroute all power and control cables 480V and below that serve the above areas. The project will include new electrical buildings with local Motor Control Centers and Distribution Panelboards and overhead and wall mounted conduit or cable trays if necessary.	\$21,100,000
J-133 Laboratory Replacement at Plant No. 1	Jun 2025	Giti Radvar	This project will replace the Central Laboratory building at Plant No. 1. The new building will be at a to be determined location onsite. The new building may also be located at an offsite property that is adjacent to the new headquarters complex (currently under construction). This existing property contains a commercial-office building and is owned by OC San, at 18350 Mt. Langley St in Fountain Valley. An additional project alternative is to renovate this commercial office space into an operating laboratory.	\$59,600,000



Design Services Request For Proposal Activity
December 2, 2024

Project Name	Mail PSA RFP	Project Manager	Scope	Construction Estimate
2-73 Fullerton - Placentia Sewer Facilities Demolition and Rehabilitation	Jul 2025	Todd Waltz	This project will demolish the Yorba Linda Pump Station in the City of Fullerton and its downstream force main, the Yorba Linda Spur Odor Station in the City of Yorba Linda, and abandon an additional 6729 feet of 12-inch VCP and manholes in Craig Regional Park and Associated Road. Flows which are currently being pumped by the Yorba Linda Pump Station east will be conveyed by gravity through the newly upsized Newhope-Placentia Trunk located in State College Boulevard to the west. Gravity sewers located in Yorba Linda Boulevard will be reconfigured to permanently divert flow away from the pump station. This project will also rehabilitate the Pioneer Branch, Kraemer Boulevard Interceptor, portions of the Rolling Hills Sub-Trunk and Carbon Canyon Dam Interceptor in the cities of Brea, Fullerton, and Placentia. This portion of the work includes construction of 30 feet of new 24-inch VCP sewer and a new 84-inch manhole, the rehabilitation of 975 feet of 15-inch VCP sewer and 48 manholes 48-inch to 84-inch manhole in diameter, and construction of various spot repairs.	\$12,400,000
P1-136 12.47 kV Switchgear Replacement at Central Generation at Plant No. 1	Oct 2025	Holly Murakami	This project will take place at the Plant No. 1 Central Generation Facilities and the 12Kv Service Center. This Project will replace medium voltage Central Generation switchgear, power distribution equipment and aged cabling. The no longer used 12Kv Service Center will be demolished and removed.	\$8,500,000